specifications. Sidewalks abutting a curb line shall be pinned to resist differential movement. Include expansion joint where needed.

- At MU, all accessible parking spaces will be "universal spaces." Parking spaces, other than disabled, will typically be 9' in width. No compact car spaces will be permitted.
- At MU locations where a parking lot abuts to lawn areas, a mowing strip will be incorporated into the design of the parking lot. A mowing strip is a strip of pavement, 18"-24" in width, on the lawn side of the curb or parking bumpers allowing the lawn to be mowed while parking spaces are occupied.
- At MU, accessible ramps adjacent to buildings will have a snow melt system installed, controlled by the Energy Management Control System. At MU, curb cuts for disabled access will use the campus standard detail. (See standard detail in appendix.)
- Preferred material for sidewalks, ramps, and other paved exterior walking surfaces is concrete. All materials must be slip resistive.
- When necessary, fire lanes will be designated to comply with applicable codes and standards and coordinated through the project manager.
- Where exterior snow melt is to be included in outdoor paved surfaces, controls for such systems will be tied back to the University's building automation system where possible.

Asphalt and Portland Cement Concrete Paving

1. Asphalt/Portland cement concrete pavement, will be designed according to the following guidelines:
   - Roadway: (rigid and flexible) American Association of State Highway and Transportation Officials, AASHTO Guidelines for the Design of Pavement Structures, most current edition.
   - Parking Lot:
     - Rigid - Portland Cement Association
     - Flexible - The Asphalt Institute
   - Walkways will have a minimum compressive strength of 4,000 psi for 28 days.
   - All exposed concrete (including precast concrete) will be air entrained according to the Chart in Division 3 in this standard.
   - Flint and chert will be limited to 1% maximum, by weight of the coarse aggregate, in all exposed concrete (cast-in-place or precast). Lignite will be limited to 0.07%, by weight of the fine aggregate in all exposed concrete. Some applications may be required to be lignite free (project manager will advise).

6. All concrete walks and drives will be constructed on a minimum of 4" of compacted crushed stone base course. Gradation of the crushed stone will be as required for Type 1 aggregate.

7. Sand will be from local sources meeting ASTM C-144 for mortar and ASTM C-33 Size 67 for concrete. If matching of color is necessary, sand for mortar and concrete will be from the following sources:

   MU - Missouri River
   UMSL - Meramec River
   UMKC - Kaw River
   S&T - Meramec River/Little Piney

8. At MU only, driving surface pavement patches for utility cuts will include 8” of concrete with #4 transverse bars (to the patch centerline) at 18” maximum centers and 2-#4 longitudinal bars. Patch will extend 1-foot minimum outside the trench. Patch surface shall be concrete with abutting concrete paving or 2” of asphaltic concrete/tack coat with abutting asphalt surface.

9. Joints and Concrete Flatwork
   - Expansion joints shall be installed to provide for thermal expansion of concrete pavements. Generally expansion joints shall be provided at the PC and PT of curves where the deflection angle is greater than 30E and intersections. If required for load transfers, expansion joints will be detailed with dowel bars to allow load transfer and expansion of the concrete slabs. Non-extruding expansion joint material will be used with expansion joints.
   - Portland cement concrete fla,b5crete

x xÀ LB¤"¤ ÄöÂ¤(ÿl.FÂ¤0ÀP x€À 0D Li ñ taí% x